INOVO PROJECT CHARTER

PROJECT NAME	PROJECT SPONSOR	PROJECT MANAGER
Inovo Snaptel IP PBX Deployment	Inovo Telecom (Pty) Ltd	Estelle Gerber

START DATE	TARGET COMPLETION
04/03/2026	30/09/2026

PROJECT OVERVIEW

PROJECT PURPOSE	Inovo Telecom requires a telephony solution suited to their client's unique communication needs. The new Snaptel PBX solution is tailored to fit the customers' current communication processes. This solution will both be scalable and will ensure maximum uptime for the client's business. This solution will enable Inovo to monitor and maintain the voice infrastructure with minimal variable costs to the business.
BUSINESS CASE	. The client is currently exploring opportunities to enhance its communication capabilities with a proprietary, scalable platform for its customer base. ICTGlobe will propose a solution to support Inovo Telecoms' telephony requirements. By deploying the agreed Snaptel solution, Inovo aims to: • **Generate New Revenue Streams:** Transition from a consumer of services to a Service Provider by entering the voice segment of the market, leveraging ICTGlobe's Vodia and Snaptel stack to support up to 15,000 user extensions, with the acknowledgement of possible future extension upscaling. • **Increase Client Retention:** Provide a carrier-grade Unified Communications as a Service (UCaaS) platform, for a JSE-listed Enterprise client that integrates deeply with their workflows. • **Market Differentiation:** Offer a tailored telephony experience that competes with Tier-1 South African telcos on features and price, including integrations with software to ensure operational accessibility for visually impaired operators within the group.

PORJECT OBJECTIVES	The Key Performance Indicators (KPI's) below will be used to measure the success of the telephony solution. **Metrics and Target Goals**: • **Infrastructure**: Establish dual-site high availability (HA) via Teraco Isando (JB1) and Rondebosch (CTI) with 10Gbps cross-connects. • **Accessibility**: To drive full user adoption, the solution must address the "Desk Experience" for every user persona, from the high-volume Switchboard to the administrative Back Office while maintaining the specialized accessibility tracks for visually impaired users. • **Scale**: Support a minimum of 10,800 extensions across multiple corporate divisions with the option to scale the solution beyond the initial committed extension quantity. • **Geographic Reach**: Active deployments in all identified provinces, ensuring smooth transitioning with minimal disruption. • **System Availability**: Achieve **99.9% uptime** to ensure business continuity for end-clients. • **Provisioning Speed**: Reduce new client setup time via custom templates.

HIGH-LEVEL SCOPE

CORE TECHNICAL	Configuration and installation of two 10Gbps cross-connects within Proxmox Clusters to provide hardware-level failover. Session Border Controller (SBC) integration for in-and-outbound voice traffic.
INFRASTRUCTURE SETUP	Deployment of Vodia on robust cloud instances (Teraco-based local hosting), to minimize latency. Snaptel Orchestrator configuration, Vodia logic mapping, and JAWS scripting and interface optimization.
REGIONAL ROUTING	Implementation of localized SIP trunking and user extensions to ensure "local' presence and routing across the identified South African provinces. This will be based on the northern and southern regional awareness and customer requirement.
TELEPHONE PROVISIONING	Evaluation and deployment of Fanvil V-Series and W-Series hardware where legacy devices (Avaya) are incompatible.
SERVICES	Two complimentary on-site installations, user training, and documentation.

PROJECT TEAM & STAKEHOLDERS

ICTGlobe Management (Pty) Ltd	
EXECUTIVE OVERSIGHT	Hannes Viljoen (CEO), Eugene Strydom (MD), Craig Green (HoE)
PROJECT MANAGER	Estelle Gerber (PM)
TECHNICAL LEAD	Gregorio Fernandes (Technical Engineer)
PRODUCT EXPERTISE	Jolene Geyser (Product Specialist)

Inovo Telecom (Pty) Ltd	
EXECUTIVE LEADERSHIP	Jan Kühn (Exec: CC Performance), Wynand Smit (CPO)
PROJECT MANAGER	Oscar Miles (PM)
TECHNICAL ARCHITECTURE	Quintin Myburgh (Technical Architect)
END-USERS	Inovo Telecom client: 10,000 minimum business extensions (UAT).

ASSUMPTIONS & CONSTRAINTS

Note**:** Given the South African context, "Loadshedding" and "Backhaul Stability" are significant environmental constraints. We assume the core infrastructure will be hosted in Tier-3 data centers with N+1 power redundancy.

ASSUMPTION	PBX will route al traffic to Inovo supplied SBS's.
ASSUMPTION	Inovo will be responsible for all field services and site installations.
CONSTRAINT	Bandwidth quality at the end-client site may vary by province; SD-WAN or dedicated Voice VLANs may be required.

HIGH-LEVEL MILESTONES & TENTATIVE PROJECT SCHEDULE

To manage the complexity of the enterprise structure, the project will be executed in a sectional phased approach.

Phase	Milestone Description	Target Date
Phase 1	**Initiation & Planning:** Information gathering, JAWS scoping, and project kick-off.	March 2026
Phase 2	**Infrastructure Setup:** Dual Teraco cross-connects and fibre backhaul live.	April 2026
Phase 3	**Development & SIT:** Software Evaluation, Testing & Configuration. Software mapping for JAWS and mass user data importing.	May 2026
Phase 4	**Pilot Deployment:** Live testing for the first identified business units. (Complimentary Site Installations: Pilot site A and B).	June 2026
Phase 5	**Divisional Rollout**: Business divisional and regional Rollout & Scale-up to 15,000 extensions (multi-province expansion).	June – Aug 2026
Phase 6	**Hypercare & Closure:** Post-migration stabilization and final handover.	Sept 2026

CRITICAL PATH

Teraco Connectivity	Physical installation of 10Gbps cross-connects.
Snaptel Development	Custom mapping and JAWS integration must be finalized for the Pilot Phase to proceed.
Data Dependency	Timely receipt of the "Business Units" operational requirements from the client.

COMMUNICATION & GOVERNANCE

WEEKLY **Project Progress Evaluation**	Project Managers to review the "Inovo Project Timeline" and % completion. Identify new risks, project bottlenecks, establish and review risk mitigation strategies.
BI-WEEKLY **Technical & Operations Sync**	Evaluate operational efficiency and identify issues or potential risks. Product experts and technical leads to troubleshoot infrastructure and software mapping.
MONTHLY **Project Steering Members**	Executive reporting, milestone overview and project "Health Check.".

RISK ASSESSMENT

Risk Event	Severity	Mitigation Strategy
Accessibility Failure	High	Early-stage SIT with visually impaired operators; iterative feedback loops.
Data Gaps	High	Standardized "Site Data" templates required prior to any site go-live.
UPN Mismatches	High	Ensure MS Entra ID "User Principal Names" matches the Vodia extension email exactly.
Legacy Hardware	Medium	For Back Office users keeping legacy phones, verify that LLDP-MED and VLAN tagging are correctly configured on the client switches to ensure voice quality
Hardware Lead Times	Medium	Maintain buffer stock of handsets for critical sites.

PROJECT APPROVALS

Inovo Telecom (Pty) Ltd			
Designation	**Name**	**Date**	**Signature**
Executive: Contact Centre Performance	Jan Kühn		
Chief Product Officer	Wynand Smit		
Technical Architect	Quintin Myburgh		
Project Manager	Oscar Miles		
ICTGlobe Management (Pty) Ltd			
Designation	**Name**	**Date**	**Signature**
Chief Executive Officer	Hannes Viljoen		
Managing Director	Eugene Strydom		
Head of Enterprise	Craig Green		
Product Specialist	Jolene Geyser		
Project Manager	Estelle Gerber		